



Briefing Agenda

- Existing Conditions
- Alternative Evaluation
- Environmental Operating Principles
- Technical and Policy Issues
- Recommended Plan



Purpose


The purpose of this briefing is to present the recommended plan for the Port Lions Feasibility Study



Corps Coastal Navigation Projects in Alaska



Port Lions, Alaska Navigation Improvements



Port Lions

- Accessible only by air and water
- Population less than 300
- Commercial, subsistence, and charter fishing drive the local economy
- Harbor is the lifeline of the community



Legislative Authority

Study Resolution, U.S. House of Representatives Committee on Public Works adopted 2 December 1970.

- "Rivers and Harbors in Alaska"
 Resolution
- Provides study authority throughout Alaska





Project Delivery Team

Federal Sponsor - Alaska District

- Julie Anderson Project Manager
- Patrick Fitzgerald Project Formulator
- Lizette Boyer Environmental Specialist
- Larry Bartlett Environmental Specialist
- Alan Jefferies Hydraulic Engineer
- Ken Boire (consultant) Economist
- Al Arruda Cost Engineer
- Chuck Wilson Geotechnical Engineer
- Karen Pontius Realty Specialist
- Greg Vanagel Office of Counsel

Non-Federal Sponsor - Alaska Department of Transportation and Public Facilities

- Ruth Carter Acting State Harbor Engineer
- Harvey Smith State Coastal Engineer



Partnering Agencies and Community Interests

Partnering Agencies

- U.S. Fish and Wildlife Service
- Alaska Dept. of Environmental Conservation
- Alaska Dept. of Natural Resources
- Alaska Dept. of Natural Resources, Habitat Division

Community of Port Lions

- Marvin Bartleson, Sr. Mayor
- Port Lions Tribal Council
- Port Lions City Council



Existing Conditions

Lack of adequate wave protection at existing harbor has resulted in the following problems:

- Year-round use of the basin reduced from about 124 to 35 vessels
- Damages to commercial and subsistence fishing vessels
- Damages to moorage system
- Increased emergency cost to tend vessels during storm events
- Shortage of regional moorage resulting in lost income
- Reduced subsistence harvesting opportunities
- Increased search and rescue operations



Existing Conditions (cont'd)



Year-round moorage reduced from about 124 to 35 vessels







Existing Conditions (cont'd)



Moorage floats damaged by excessive wave climate

Damaged segment of moorage float washed ashore






Existing Conditions (cont'd)



Formulation Objectives

- Reduce wave damages
- Maintain nearshore fish passage
- Protect eel grass beds
- Maintain Settler Cove water circulation





Alternatives Considered

No Action

Do nothing

Non-structural

- Remove vessels from water
- Seek shelter in other harbors

Structural

- Floating breakwaters
- Rubblemound breakwaters



Alternatives Considered (cont'd)

No Action

- Vessels and mooring system damages continue
- Year round use of basin will continue to be significantly reduced
- Over-crowding continues to cause increased operating and maintenance costs
- Vessels must travel to alternate harbors outside the region

No Action alternative eliminated from further consideration



Alternatives Considered (cont'd)

Non-structural

- Remove vessels from water
 - > Dry storage can damage vessels and is expensive
 - > No developable upland for boat storage exists near the harbor
 - Vessels not readily available for use
- Seek shelter in other harbors
 - > Other regional harbors overcrowded with long wait lists
 - Cost of travel is high
 - Vessels not readily available for use



Non-structural alternatives eliminated from further consideration

Alternatives Considered (cont'd)

Structural

- Floating breakwaters
 - > Preferred with regard to marine habitat
 - > Suited for the smaller southwest waves
 - Inadequate against ocean waves from the northeast
- Rubblemound breakwaters
 - > Adequate for larger northeast waves
 - Expect to be more cost-effective than a floating breakwater for protection from the southwest waves given the shallow water depths



Combination of structural measures would address navigation problems at Port Lions

Alternative Evaluation

Initial Alternatives

- 8 Alternatives
- Alternatives used combinations of floating and rubblemound breakwaters
- Evaluation based on preliminary designs and cost estimates
- Top 3 alternatives selected for further detailed evaluation





Final Array of Alternatives

Alternative 1A

- 700-foot rubblemound breakwater
- 732-foot floating breakwater
- Extend existing main and stub breakwaters
- Repair/replace float system

Alternative 1B

- 700-foot rubblemound breakwater
- 860-foot rubblemound breakwater
- Extend existing main and stub breakwaters
- Repair/replace float system



Alternative 3B

- 1,360-foot rubblemound breakwater
- Extend existing main and stub breakwaters
- Repair/replace float system



NED Plan Selection

Item	Alt. 1A (\$)	Alt. 1B (\$)	Alt. 3B (\$)
Project Cost	10,050,000	9,885,000	9,831,000
Interest During Construction	<u>262,000</u>	<u>258,000</u>	<u>257,000</u>
NED Investment Cost	10,312,000	10,143,000	10,088,000
Annual NED Cost	598,000	588,000	585,000
Annual OMRRR	35,000	25,000	25,000
Total Annual NED Cost	633,000	613,000	610,000
Annual Benefits	884,000	884,000	884,000
Annual Net Benefits	251,000	271,000	274,000
Benefits to Cost Ratio	1.4	1.4	1.5



Alternative 3B selected as NED Plan

NED Plan Selection (cont'd)

Alternative 3B selected as NED Plan

- Maximized net NED benefits
- Minimized project footprint
- Minimized adverse impacts to eel grass beds
- Minimized disruption to water circulation patterns

NED Plan ultimately carried forward as Recommended Plan



Mitigation

Key environmental factors designed into NED Plan

- Maintain existing nearshore gap
- Provide nearshore gap for the new breakwater
- Round corners of breakwater to provide adequate water circulation within harbor
- Configure breakwater alignment to minimize disruption of water circulation within Settler Cove

Additional mitigation

- Construction windows to avoid salmon migration
- Isolate in-water construction as necessary to minimize turbidity
- Harbor signage on safe operating practices (sponsor)
- Stationary light shields to reduce bird strikes (sponsor)
- Harbor Management Plan (sponsor)



Public Involvement Process

Public meeting May 2002

Teleconference with Port Lions City Council December 2003

Public meeting April 2004



Collaboration

Examples of project collaboration

Nearshore Gaps

- Alaska Dept. of Transportation
- U.S. Fish and Wildlife Service
- Alaska Dept. of Natural Resources, Habitat Division

Settler Cove Water Circulation

- Alaska Dept. of Transportation
- U.S. Fish and Wildlife Service
- Community interests, local fishers, and harbor users

Harbor Water Quality

- Alaska Dept. of Environmental Conservation
- Alaska Dept. of Transportation
- U.S. Fish and Wildlife Service
- Community interests, local fishers, and harbor users



Environmental Operating Principles

1. Environmental Sustainability

- Self-flushing harbor ensures adequate water quality
- Breakwater design minimal O&M

2. Interdependence of life and the physical environment

- Minimized impacts to the marine environment
 - Avoided eel grass beds
 - Provided nearshore gaps for fish passage

3. Seek balance and synergy between human and natural systems

 Coordinated alternative development with the community members, harbor users, and state and federal agencies



Environmental Operating Principles

4. Continue to accept corporate responsibility and accountability

- Addressed agency and public concerns
- Identified and mitigated all project impacts

5. Assess and mitigate cumulative impacts to environment

- Project designed to minimize impacts
 - Minimize project footprint
- Unavoidable impacts fully mitigated
- Construction windows to avoid salmon migration
- Isolate in-water construction as necessary to minimize turbidity



Environmental Operating Principles (cont'd)

6. Build and share knowledge

- Multi-partner effort to obtain study information to arrive at a recommended plan
- Utilized local knowledge of wind and wave conditions
- Utilized local and regional knowledge of vessel practices

7. Respect the views of individuals and groups

 Listened to and incorporated views of others through public and team meetings



Independent Technical Review

ITR Conducted January - March 2005

ITR Certification April 1, 2005

ITR Issues and Resolution

- All comments resolved through discussion or further clarification within the report
- No significant revisions or analyses required to resolve comments



Policy Compliance

Alternative Formulation Briefing May 25, 2005

Policy Issues and Resolution

- No significant revisions or analyses required to resolve comments
- Multiplier for Donated Labor Recognized that some aspects
 of volunteer labor may be valid for determination of benefits.
 However, a standard evaluation procedure has not been
 developed. Report revised to include only actual expenses
 for the harbormaster and city employees that can be avoided
 in the with-project condition.



Policy Compliance (cont'd)


Policy Issues and Resolution – New HQ comments Jan 2006

- CWCCIS Ensure use of latest cost indices
- MCACES narrative Provide cost estimate narrative

Revisions to report will be addressed in a February 2006 addendum



Recommended Plan





General Navigation Features (GNF)

<u>ltem</u>	Cost (\$000)
Mobilization & Demobilization	946
Breakwaters	6,552
Preconstruction, Engineering, & Design	597
Construction Management	697
LERR(GNF) - Administrative Cost	<u>1</u>
TOTAL GNF	\$ 8,793



Non-Cost Shared Items

Item Cost (\$000)

Aids To Navigation (Federal) 10

Local Service Facilities

Floats (Non-Federal) 1,038



Total First Cost: \$9,841,000

	Total	Federal	Non-Federal
<u>ltem</u>	<u>(\$000)</u>	<u>(\$000)</u>	<u>(\$000)</u>
General Navigation Features	8,793	7,914	879
Aids to Navigation	10	10	0
Local Service Facilities:	1,038	0	1,038
LERR Credit	0	0	0
Additional Funding Requirements:		(879)	879
GNF LERR Credit		0	0
Total	\$9,841	\$ 7,044	\$ 2,797



Investment Costs:

General Navigation Features 8,793,000
Local Service Facilities 1,038,000
LERR 0
Interest During Construction 257,000
Total Investment Cost \$10,088,000

Annual Costs:

Interest and Amortization 585,000 Amortized OMRR&R 25,000

Total Average Annual Cost \$610,000



Annual NED Benefits \$884,000

Primary benefits from additional wave protection at Port Lions:

- Reduced harbor damages
- Reduced vessel damages
- Reduced harvest cost
- Reduced local emergency cost
- Reduced water taxi service

Other direct benefits include

- Increased subsistence opportunities
- Harbor of refuge
- Reduced search and rescue



Total Project First Costs \$9,841,000

Average Annual Benefits \$ 884,000

Average Annual Costs \$ 610,000

Benefit-Cost Ratio 1.5

(Price Level = October 2004; Discount Rate = 5 3/8%)



Navigation Improvements Port Lions, Alaska

Project Sponsor Presentation to the Civil Works Review Board

By Ruth Carter, PE Alaska Department of Transportation and Public Facilities

- The State of Alaska, Department of Transportation & Public Facilities strongly supports completion of the Port Lions Navigation Improvements project. This is evidenced in the departments budget and priority listings.
- Currently the state owns and maintains the harbor, which is operated by the local community. The floats within Port Lions harbor have sustained severe damage due to the lack of adequate wave protection. The state is committed to repairing these inner harbor facilities once the wave protection identified in this study is built.
- The department has worked cooperatively with the Alaska District Corps and City of Port Lions to select the preferred Alternative 3B from eight initial layouts.

Questions?



Civil Works Review Board

MSC Commander's Briefing

Port Lions, Alaska Navigation Improvements Final Feasibility Report & EA

COL(P) John W. Peabody
Commander, Pacific Ocean Division
Represented by
COL Raymond K. Scrocco
Acting Commander, Pacific Ocean Division



26 January 2006

Quality Assurance

- Participated in milestone meeting during report development and coordinated with RIT
- Confirmed proper certification: ITR, Legal, Policy Compliance
- Determined that public, key partners, and stakeholder input considered



Pacific Ocean Division Position

- Concur with Alaska Engineer District
 Commander's findings and recommendations
- Confirmed that report complies with applicable laws and policies
- Meets CW Strategic Plan goal of balanced solution to water resource need
- Positive response to draft Report of Chief of Engineers expected
- Recommend approval of the report for State and Agency Review



Questions?



Civil Works Review Board

Significant Policy Review Concerns

Port Lions, Alaska Navigation Improvements Final Feasibility Report & EA

Robert McIntyre
Office of Water Project Review
Policy and Policy Compliance Division

Washington, DC - January 26, 2006



Areas of Policy Concern:

- Moorage Capacity Limits
- Multiplier for Donated Labor
- Associated Costs Expansion Berths
- Incremental Justification Plan Features
- Outdated Inflation Factors
- MCACES Cost Display



Moorage Capacity Limits

Concern: AFB materials did not show a detailed layout of docked boats after breakwater construction. From AFB material not apparent how 124 fishing vessels could fit into basin.

Reason: Guidance for CW projects requires accurate presentation of project features in order to determine benefits, and overall justification

Resolution: District revised the report to include a float layout for the 124 fishing vessels.



Multiplier Donated Labor

Concern: AFB materials included 3,000 hours of donated labor at \$14 per hour plus a 2.5 fringe benefit factor for benefits of \$114, 500. No procedure for using donated labor as a benefit. No administrative or fringe benefit savings since there is no payroll.

Reason: A standard evaluation procedure for evaluation of volunteer labor has not been developed. Highly questionable NED benefit category.

Resolution: Draft and final report have been revised to include only actual expenses in preventing storm damages to existing dock and moored fleet.



Associated Costs - Expansion Berths

Concern: The AFB materials pointed out that 100 berths were built but only 35 vessels can safely use the current moorage. Have the associated float costs of 124 expansion berths been included in the analysis?

Resolution: The district verified that the costs of the float expansion were included in the project.



Incremental Justification - Plan Features

Concern: AFB materials did not show incremental justification for the new breakwater and two breakwater extensions to the existing project.

Reason: Incremental justification is required for all plan features.

Resolution: District explained that plan features were determined by design criteria for a safe harbor. While the various breakwaters are physically separable, they are not functionally separable. All are needed to attain the benefits, therefore incremental justification of each element is not warranted.



Outdated Inflation Factors

Concern: The final report Total Project Cost Summary stated that the Civil Works Construction Cost Index System (CWCCIS) dated 27 Mar 98, was used for the calculation of the Fully Funded Estimate. The project costs could be understated due to the application of outdated inflation factors.

Reason: The latest CWCCIS dated 31 March 2004 should be used to update unit prices and project cost features.

Resolution: The Total Project Cost Summary should be revised and corrected base on the latest CWCCIS.

Resolution Impact: Concern to be resolved by revisions to final report



MCACES Cost Display

Concern: The final report MCACES estimate did not include a narrative to support the development of costs, assumptions, construction duration, and contingency development.

Reason: Without a narrative the reviewer has difficulty understanding the basis and assumptions used in the development of the estimate. Also, the narrative provides the district with a historical basis as the project proceeds and would bring it into conformance with ER 1110-2-1302.

Resolution: The cost development narrative should be included in the final report MCACES estimate.


Resolution Impact: Concern to be resolved by revisions to final report



HQUSACE Policy Compliance Review Team RECOMMENDATION

Release the report and EA for S&A Review







#1 Face-to-Face Community Interaction

Some community concerns (wave protection and icing) were not addressed in a timely manner. PDT was surprised to learn of these concerns. Although concerns were ultimately addressed and consensus reached, it could have be accomplished in a more responsive manner.



TAKE AWAY: Future studies should schedule and budget for more regularly scheduled community meetings

#2 Economics in the Lead

Initial study efforts focused on economic analysis to determine the potential for the full feasibility study resulting in a positive project. This was done to lower the risk of expending full study cost on a study that does not result in a recommended plan.

TAKE AWAY: Utilize alternative study methods to focus on critical issues early in the study and increase local sponsor confidence in the study process



#3 Collaboration Pays

PDT closely coordinated with community and State to resolve concerns of water circulation during the study

TAKE AWAY: Conduct frequent short meetings among study interests to identify critical issues early and minimize risk of last-minute surprises



#4 Underwater Video Camera

Use of an underwater video camera provided definitive mapping of critical aquatic habitat and identified aquatic resources

TAKE AWAY: Continue to use new technologies to definitively identify important biological resources and minimize adverse project impacts to the environment



#5 Study Costs

Comparison of study scoping cost indicated that the Corps was significantly less expensive than a private contractor

TAKE AWAY: It's a myth that private sector engineering is always less expensive than the Corps



Questions?



Civil Works Review Board

LESSONS LEARNED

Port Lions, Alaska Navigation Improvements Final Feasibility Report & EA

COL(P) John W. Peabody
Commander, Pacific Ocean Division
Represented by
COL Raymond K. Scrocco



26 January 2006

#1 Open lines of communication facilitated the study approval process.

TAKE AWAY: Consistent two-way communication between POA, POD, and Headquarters minimized the impacts created by the distances between the offices.



Questions?

