

ENGCW-ES

DEPARTMENT OF THE ARMY
Office of the Chief of Engineers
Washington, D. C. 20314

EM 1110-2-1902

Manual
No. 1110-2-1902

1 April 1970

ENGINEERING AND DESIGN
Stability of Earth and Rock-Fill Dams

Table of Contents

<u>Paragraph</u>		<u>Page</u>
1.	Purpose.....	1
2.	Scope	1
3.	Applicability.....	1
4.	References.....	1
	a. EM 1110-2-2300	1
	b. Other Engineer Manuals	1
	c. Selected References.....	2
5.	Notation.....	2
6.	Basic Design Considerations.....	2
7.	Causes of Unsatisfactory Embankment Performance	3
	a. Shear Failure	3
	b. Excessive Deformation.....	4
	c. Liquefaction	5
8.	Special Problems	5
	a. Progressive Failure.....	5
	b. Problem Shales.....	6
	c. Rate of Fill Placement	7
9.	Design Shear Strengths.....	7
	a. Laboratory Tests.....	7
	b. Selection of Design Shear Strengths.....	13
10.	Methods of Stability Analysis.....	14
11.	Design Conditions for Analysis	15
	a. Case I: End of Construction	15
	b. Cases II and III: Sudden Drawdown.....	16
	c. Case IV: Partial Pool	18
	d. Case V: Steady Seepage with Maximum Storage Pool	19
	e. Case VI: Steady Seepage with Surcharge Pool.....	19
	f. Case VII: Earthquake.....	19
	g. At-Rest Earth Pressure Analyses.....	20

EM 1110-2-1902
1 April 1970

<u>Paragraph</u>	<u>Page</u>
12. Factors of Safety.....	26
13. Presentation in Design Memoranda.....	26
14. Use of Electronic Computers.....	28

APPENDIX I
References

APPENDIX II
Notation

APPENDIX III
Estimating the Lowering of the Seepage Line
in Pervious Upstream Embankment Zones
During Reservoir Drawdown

APPENDIX IV
Simplified Procedures for Preliminary
Determination of Embankment Slopes

APPENDIX V
Infinite Slope Analysis for Cohesionless Soils

APPENDIX VI
Modified Swedish Method of Analysis
Using Slice Procedure

1. General.....	VI-1
2. Procedure of Finite Slices	VI-1
3. Graphical Integration Procedure	VI-5
4. End of Construction--Case I	VI-10
5. Sudden Drawdown--Cases II and III.	VI-10
6. Partial Pool, Upstream Slope--Case IV.	VI-12
7. Steady Seepage, Downstream Slope--Cases V and VI . .	VI-13
8. Earthquake--Case VII	VI-14

PLATES

<u>No.</u>	
VI-1	Modified Swedish Method, Finite Slice Procedure, No Water Forces
VI-2	Modified Swedish Method, Finite Slice Procedure, Sudden Drawdown Impervious Embankment

<u>No.</u>	
VI-3	Modified Swedish Method, Finite Slice Procedure with Steady Seepage, Water Forces
VI-4	Modified Swedish Method, Finite Slice and Graphical Integration Procedure, Earthquake Loading
VI-5	Modified Swedish Method, Graphical Integration Procedure, No Water Forces
VI-6	Modified Swedish Method, Graphical Integration Procedure, Sudden Drawdown
VI-7	Modified Swedish Method, Graphical Integration Procedure, Steady Seepage, Water Forces
VI-8	Stability Analysis, Case I - End of Construction, Upstream Slope, Modified Swedish Method, Finite Slice Procedure
VI-9	Stability Analysis, Case I - End of Construction, Modified Swedish Method, Graphical Integration Procedure
VI-10	Stability Analysis, Case II - Sudden Drawdown, Upstream Slope, Modified Swedish Method, Finite Slice Procedure
VI-11	Stability Analysis, Embankment with Central Core and Semipervious Shell, Case II - Sudden Drawdown, Modified Swedish Method, Finite Slice Procedure
VI-12	Stability Analysis, Case II - Sudden Drawdown, Upstream Slope, Modified Swedish Method, Graphical Integration Procedure
VI-13	Stability Analysis, Case IV - Partial Pool, Upstream Slope, Modified Swedish Method, Finite Slice Procedure
VI-14	Stability Analysis, Case IV - Partial Pool, Upstream Slope, Modified Swedish Method, Graphical Integration Procedure
VI-15	Stability Analysis, Case V - Steady Seepage, Downstream Slope, Max Storage Pool, Modified Swedish Method, Finite Slice Procedure
VI-16	Stability Analysis, Case V - Steady Seepage, Downstream Slope, Max Storage Pool, Modified Swedish Method, Graphical Integration Procedure

EM 1110-2-1902
1 April 1970

No.

- VI-17 Stability Analysis, Case VII - Earthquake, Steady Seepage, Downstream Slope, Modified Swedish Method, Finite Slice Procedure
- VI-18 Stability Analysis, Case VII - Earthquake, End of Construction, Modified Swedish Method, Graphical Integration Procedure

Paragraph

Page

APPENDIX VII
Wedge Analysis

1.	General.....	VII-1
2.	Basic Principles.....	VII-1
3.	Basic Criteria	VII-2
4.	End of Construction--Case I.....	VII-5
5.	Sudden Drawdown--Cases II and III	VII-8
6.	Partial Pool, Upstream Slope--Case IV	VII-11
7.	Steady Seepage with Maximum Storage Pool--Case V	VII-12
8.	Steady Seepage with Surcharge Pool--Case VI	VII-13
9.	Earthquake	VII-14

PLATES

No.

- VII-1 Stability Analysis, Wedge Method
- VII-2 Direction of Resultant Earth Forces and Active and Passive Sliding Planes, Wedge Method
- VII-3 Use of Conjugate Stresses
- VII-4 Stability Analysis of Embankment with Central Core,
Case I - End of Construction, Wedge Method
- VII-5 Stability Analysis of Embankment with Inclined Core,
Case I - End of Construction, Wedge Method
- VII-6 Stability Analysis, Embankment with Central Core
and Semipervious Shell, Case II - Sudden Draw-
down, Wedge Method

<u>No.</u>	
VII-7	Stability Analysis, Embankment with Inclined Core and Free-Draining Shell, Case II - Sudden Drawdown, Wedge Method
VII-8	Stability Analysis, Embankment with Inclined Core and Free-Draining Shell, Case IV - Partial Pool, Wedge Method
VII-9	Stability Analysis, Embankment with Central Core, Case V - Steady Seepage, Wedge Method
VII-10	Stability Analysis Embankment with Central Core, Case VI - Surcharge Pool, Wedge Method
VII-11	θ_A vs ϕ_D for Cohesionless Soil, Coulomb Active Sliding Plane for Active Wedge Beneath Negative Slope
VII-12	K_A vs ϕ_D for Cohesionless Soil, Coulomb Active Sliding Plane for Active Wedge Beneath Negative Slope

<u>Paragraph</u>	<u>Page</u>
APPENDIX VIII	
Evaluation of Embankment Stability During Construction	
1. Basic Consideration	VIII-1
2. Development of Pore Water Pressure During Construction	VIII-1
3. Installation and Uses of Piezometers	VIII-4
4. Evaluation of Embankment Stability	VIII-5

<u>No.</u>	
VIII-1	Pore Pressures in Partially Saturated Soils, No Drainage During Loading
VIII-2	Pore Pressures in Partially Saturated Soils, Effect of Complete Dissipation of Pore Pressure Between Construction Seasons
VIII-3	Pore Pressures in Partially Saturated Soils, Effect of Partial Dissipation of Pore Pressure Between Construction Seasons

EM 1110-2-1902
1 April 1970

<u>No.</u>	
VIII-4	Pore Pressure Coefficients A and B
VIII-5	Development of Excess Pore Water Pressures
VIII-6	Data for Estimating Pore Pressures in Q Test
VIII-7	Undrained Shear Strength for Various Ratios of $\bar{\sigma}_1/\bar{\sigma}_3$ at Start of Shear
VIII-8	Undrained Shear Strength for Field Stress Conditions